


15-007-00076-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 2 Twp. 32 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SW/SW/SE
Lease Owner Purcell-Mull Drilling Co., Inc.
Lease Name Lake Well No. R-1
Office Address 6405 East Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10-6- 19 55
Plugging completed 10-10- 19 55
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4701 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	190'	None
				5 1/2"	4014'	3437'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging started 10-6-55 and completed 10-10-55. Measured in to TD 3874'

and put in 55' rocks and 5 sacks of cement. Shot casing off at 3430' and pulled pipe out of hole. Plugged well as follows: plugged with heavy mud; set permanent rock bridge at 225' and dumped in 25 sacks of cement. Filled hole with heavy mud to 35' of top and capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address P. O. Box 221, Gt. Bend, Kans.


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Frank H. Purcell (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank H. Purcell
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 55

My commission expires January 28, 1957

Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1955
10-21-55
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLERS LOG

COMPANY : FURCHILL-HELL DRILLING COMPANY, INC. ROTARY DRILLING COMPLETED: 11-15-54
 CONTRACT NO. : FURCHILL-HELL DRILLING COMPANY, INC. DRILLING COMPLETED: 12-4-54
 CASING RECORD: 150' of 3 5/8" Surf. Casg. cemented with 150 sacks cement. LOCATION: LOT A-1
 50 33 27, Sec. 2-32-247
 Barber County, Kansas
 101 1/2' of 5 1/2" casing cemented with 150 sacks cement

(Figures indicate bottom of formation - measurements from top of Rotary Drilling.)

Clay	20	Shale & Lime	3687
Red Bed	1009	Lime & Shale	3975
Shale & Shells	1575	Sand	3735
Shale & Lime	1965	Lime & Shale	3908
Lime	2532	Lime	4581
Lime & Shale	3217	Cherty Lime	4508
Shale & Lime	3127	Shale & Lime	4077
Lime & Shale	3163	Lime	4701 R.T.C.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

FURCHILL-HELL DRILLING COMPANY, INC.

Frank L. Furchill
 FRANK L. FURCHILL SECRETARY

STATE OF KANSAS }
 COUNTY OF BARBER)

Subscribed and sworn to before me this 7th day of December, 1954.

Ethel Zimmerman
 ETHEL ZIMMERMAN COUNTY CLERK

MY COMMISSION EXPIRES: January 28, 1957.

RECEIVED STATE CORPORATION COMMISSION

PLUGGING
 SEC 2 T 32 R 14W
 PAGE 4 LINE 41

10-21-55