


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 1 Twp. 32s Rge. 14 ~~X~~ (W)

Location as "NE/CNW*SW*" or footage from lines. C SW SE
Lease Owner Time Petroleum Company
Lease Name Lake Well No. 1
Office Address 815 Union National Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-18-64 1964
Application for plugging filed 4-~~18~~-17 1964
Application for plugging approved 4-17 1964
Plugging commenced 4-17 1964
Plugging completed 4-18 1964

NORTH



Locate well correctly on above
Section Plat

Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	292'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 285' plug - 1/2 Sk Hulls & 25 sacks Cement
Mud to 40' plug - 1/2 Sk Hulls & 10 sacks Cement
2 sacks cement in Rathole - 4-18-64

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1964

S-5-64

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 1964

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY:
 CONTRACTOR:
 FARM:
 LOCATION:
 COMMENCED:
 COMPLETED:

Time Petroleum Company
 LEBEN DRILLING, INC.
 Lake #1
 C SW SE Section 1-32s-14w
 Barber County, Kansas
 4-6-64
 4-18-64

RECEIVED
 STATE CORPORATION COMMISSION

APR 23 1964
 4-23-64

0	130	CONSERVATION DIVISION Wichita, Kansas	Red Bed and Rock
130	272		Red Bed and Gyp
272	1400		Red Bed and Shale
1400	1755		Red Bed, Shale and Gyp
1755	2620		Lime and Shale
2620	3710		Shale and Lime
3710	3990		Lime and Shale
3990	4420		Lime
	4420		Rotary Total Depth - D & A

Set 8 5/8" Surface Casing @ 292' cemented with 225 sacks common 3% c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lake #1, located C SW SE of Section 1, TOWNSHIP 32 South, Range 14 West, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 LESLIE KITE

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 21st day of April, 1964.

Ulanda Nichols

 ULANDA NICHOLS

My commission expires; April 1, 1967