

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,017-00-00

LEASE NAME Ricke Estate

WELL NUMBER #5

SPOT LOCATION 150'W, C NW SW

SEC. 7 TWP. 32S RGE. 10 (E or W)

COUNTY Barber

Date Well Completed 3/18/85

Plugging Commenced 3/18/85

Plugging Completed 3/19/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR HUMMON CORPORATION

ADDRESS 400 One Main Place

PHONE # (316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? _____

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4696

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Sand & Red Rock	0	228	8-5/8	221	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged as follows by Sun Cementing: plugged @ 800' w/ 50 sx; 370' w/ 50sx, bridge @ 40' w/ 15sx filled to top, 15 sx in rat-hole, 10sx in mouse-hole, w/ 60/40 Poz, 2% gel, 3% CC, completed @ 12:30 A.M. 3/19/85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BIG-H DRILLING, INC. License No. 5148
Address 400 One Main Place, Wichita, Ks. 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Wiber D. Berg (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wiber D Berg

(Address) 400 One Main Place
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 19 85

Sandra L. Mendoza
Notary Public

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. _____

RECEIVED
STATE CORPORATION COMMISSION
04-23-1985
APR 23 1985
CONSERVATION DIVISION
Wichita, Kansas

My Commission expires: 2/13/86

DRILLERS LOG

15-007-22017-0000

#5 Ricke Estate

CASING RECORD:
8-5/8" @ 221
w/ 200 sx. cement

COMPANY: Hummon Corporation
CONTRACTOR: Big-H Drilling, Inc.
COMMENCED: March 7, 1985
COMPLETED: March 19, 1985

DESCRIPTION:
150' West of
C NW SW
Sec 7-32S-10W
ELEVATION: 1521 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Red Rock	0	228	
Red Bed & Shale	228	633	
Red Bed & Shale & Lime	633	1236	
Shale & Lime	1236	1648	
Lime & Shale	1648	1906	
Shale & Lime	1906	2293	
Lime & Shale	2293	2380	
Shale & Lime	2380	2815	
Lime & Shale	2815	3000	
Shale & Lime	3000	3392	
Lime & Shale	3392	3610	
Shale & Lime	3610	3618	
Lime & Shale	3618	3726	
Shale & Lime	3726	3813	
Lime & Shale	3813	4052	
Shale & Lime	4052	4168	
Lime & Shale	4168	4328	
Shale & Lime	4328	4406	
Chert	4406	4421	
Lime & Shale & Chert	4421	4494	
Lime & Chert & Shale	4494	4572	
Shale & Lime	4572	4632	
Lime & Shale	4632	4696	
RTD		4696	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Big-H Drilling, Inc.

Cindy L. Romig
Cindy L. Romig

Subscribed and sworn to before me this 25th day of March, 1985.

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT EXP 2/13/86

Sandra L. Mendoza
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1985

04-23-1985

CONSERVATION DIVISION
Wichita, Kansas