

15-007-30239-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 5 Twp 32S Rge 10W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW
Lease Owner Martin & Keller
Lease Name Garrett Well No. 1
Office Address 1035 Kennedy Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-8-66 19
Application for plugging filed 4-7-66 19
Application for plugging approved 4-7-66 19
Plugging commenced 4-7-66 19
Plugging completed 4-8-66 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 215', set plug with 1/2 sk. hulls and 25 sks. cement
Filled hole with mud to 40', set plug with 1/2 sk. hulls and 10 sks. cement
put 2 sks. cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1966

CONSERVATION DIVISION
Wichita, Kansas

04-14-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF ~~KAN~~ KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 1966

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: Martin & Keller
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: GARRETT #1
 LOCATION: SW NW Sec. 5-32S-10W
 BARBER COUNTY, KANSAS
 COMMENCED: 3-24-66
 COMPLETED: 4-8-66

0	490	Redbed
490	1280	Shale
1280	1525	Shale, Anhydrite Stringers
1525	1890	Shale, Lime
1890	2125	Lime
2125	2365	Lime, Shale
2365	2550	Shale
2550	3400	Lime, Shale
3400	3567	Lime
3567	3858	Lime, Shale
3858	4357	Lime
4357	4402	Lime, Shale
4402	4500	Lime, Shale, Chert
4500	4510	Mississippi
4510	4557	Chert
4557	4609	Mississippi
4609	4640	Lime, Chert
4640	4707	Lime, Chert
4707	4741	Kinderhook
4741	4751	Lime, Shale
4751	4810	Kinderhook, Viola
4810	4824	Lime, Chert
4824	4830	Sand
4830	4840	Simpson
4840	4850	Sand
	4850	RTD - D. & A.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 14 1966
 04-14-1966
 CONSERVATION DIVISION
 Wichita, Kansas

 Set 8 5/8" used surface casing @ 221' cemented with 185 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Garrett #1 well, located
 SW NW of Section 5, Township 32 South, Range 10 West, Barber County,
 Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 12th day of April, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967