

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Harper

County, Sec. 16 Twp. 32 Rge. 7 (X) (W)

Location as "NE/CNW&SW" or footage from lines SE SW NE

Lease Owner Sohio Petroleum Company

Lease Name Larsen Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-17- 1955

Application for plugging filed 3-17- 1955

Application for plugging approved 3-19- 1955


Plugging commenced 3-17- 1955

Plugging completed 3-17- 1955

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4970' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	295'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4970'-270' Heavy Mud  
270'-210' Solid Bridge w/1 sack HULLS; 20 sacks cement.  
210'-40' Heavy Mud  
40'-Cellar Bridge & 5 sacks cement

Rec'd  
03-23-1955

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address Wichita, Kansas

STATE OF Kansas COUNTY OF Russell ss.  
J. H. Bond (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1955

Quentin B. Brown

Notary Public.

My commission expires January 24, 1959

PLUGGING  
FILE SEC 16 T 32 R 7W  
BOOK PAGE 105 LINE 26

# WELL LOG

15-077-00037-00-00

COMPANY SOHIO PETROLEUM COMPANY

SEC. 16 T. 32S R. 7W

FARM Larsen

NO. 1

LOC. SE SW NE


TOTAL DEPTH 4970

COUNTY Harper

COMM. 2-23-55

COMP. 3-17-55

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 289 (225 SX)

ELEVATION unknown

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Surface Sand & Red Bed
940	Red Bed & Shale
1050	Shale & Shells
1070	Anhydrite
1465	Shale & Shells
2200	Lime & Shale
2470	Shale
2595	Lime & Shale
2885	Shale & Shells
3030	Lime & Shale
3160	Shale, Lime & Sand
3245	Shale & Lime
3455	Lime & Shale
3582	Shale & Lime
3672	Sand
3862	Shale
4195	Lime
4210	Shale
4255	Lime & Shale
4315	Lime
4372	Lime & Shale
4410	Cherty Conglomerate
4560	Cherty Lime
4589	Cherty Lime & Shale
4616	Cherty Lime
4657	Lime & Shale
4695	Shale
4736	Lime & Shale
4738	Lime
4803	Sand & Shale
4812	Shale & Sand
4870	Sand & Shale
4898	Lime & Shale
4914	Shale
4937	Lime & Shale
4970	Arbuckle

Rec'd  
03-27-1955

State of KANSAS }  
 County of SEDGWICK } SS:

R.T.D. 4970'

**PLUGGING**  
 SEC 16 T 32 R 7W  
 PAGE 105 LINE 26

I, Karl E. Becker of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Larsen well.

*Karl E. Becker*  
Karl E. Becker

Subscribed and sworn to before me this 25th day of March 19 55

My Commission Expires: 11 August 1958

*[Signature]*  
NOTARY PUBLIC