


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-077-00228-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 17 Twp. 32S Rge. 7 (X) (W)
Location as "NE/CNWxSWx" or footage from lines SW SW NE
Lease Owner Aurora Gasoline Co.
Lease Name Garber Well No. 1
Office Address 802 Union National Bank Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-11 19 56
Application for plugging filed 8-11 19 56
Application for plugging approved 8-11 19 56
Plugging commenced 8-11 19 56
Plugging completed 8-11 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4976 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3275			204'	
Oriad		3400		8 5/8		
Kansas City		3868				
Mississippi		4401				
Viola		4726				
Simpson Dolomite		4774				
Simpson Sand		4790				
Arbuckle		4932				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 200'. Halliburton plug cemented with 20 sacks cement. Mud and hulls to 35' and top plug set and cemented with 10 sacks cement. Finish plugging with 10 sacks cement as a cap.

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1958

CONSERVATION DIVISION
Wichita, Kansas

08-18-1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Joe W. Cain (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain
Box 627 - Augusta, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 56

Ruth T. Carter
Notary Public.

My commission expires October 23, 1958.

PLUGGING
FILE SEC. 17 T. 32 R. 7W
BOOK PAGE 89 LINE 40

Company - Aurora Gasoline Co.
 Contractor - L. C. Smitherman Drlg. Co.
 Commenced - 7-20-56
 Completed - 8-12-56
 Total Depth - 4976'
 Initial Prod. - D & A

Location: SW SW NE, Sec. 17-32S-7W,
 Harper Co., Kansas
 Elevation:
 Casing: 8 5/8" - 204' Cemented w/200 Skts.

Figures Indicate Bottoms of Formations:

Depth	Formation	Depth	Formation
0 - 5	Cellar	4829 - 4851	Shale W/Sand Strks.
5 - 105	Sand, Clay, Lime Strks.	4851 - 4872	Sand (Simpson)
105 - 175	Clay, Shale W/Lime Shells	4872 - 4883	Sand & Shale
175 - 204	Lime W/Shale Brks.	4883 - 4921	Shale - Sand Strks.
204 - 757	Shale, Red Bed, Lime Strks.	4921 - 4926	Sand & Shale
757 - 849	Shale & Lime Strks.	4926 - 4976	Lime (Arbuckle)
849 - 1285	Lime & Shale	4976 - R. T. D.	
1285 - 1300	Salt		
1300 - 1325	Lime & Shale		
1325 - 1375	Lime W/Shale Brks.		
1375 - 1450	Shale W/Lime Strks.		
1450 - 1646	Lime & Shale		
1646 - 1813	Lime		
1813 - 2110	Lime & Shale		
2110 - 2216	Shale W/Lime Strks.		
2216 - 2400	Shale & Lime		
2400 - 2575	Lime & Shale		
2575 - 2708	Shale & Lime		
2708 - 3600	Lime & Shale		
3600 - 3678	Shale		
3678 - 3775	Lime & Shale		
3775 - 3864	Shale W/Lime Strks.		
3864 - 4042	Lime		
4042 - 4107	Lime W/Shale Brks.		
4107 - 4170	Lime & Shale		
4170 - 4230	Lime		
4230 - 4275	Lime W/Shale Brks.		
4275 - 4323	Lime & Shale		
4323 - 4394	Shale & Lime Cherty		
4394 - 4401	Shale & Lime		
4401 - 4428	Chert (Mississippi)		
4428 - 4593	Lime (Mississippi)		
4593 - 4624	Lime - Mississippi - Cherty		
4624 - 4650	Lime W/Shale		
4650 - 4681	Lime (Miss.) W/Shale Strks.		
4681 - 4734	Lime W/Shale		
4734 - 4745	Lime (Viola)		
4745 - 4769	Shale W/Lime		
4769 - 4790	Lime & Shale Brks.		
4790 - 4800	Lime & Shale W/Sand Strks.		
4800 - 4829	Sand (Simpson)		

08-18-1956

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Garber #1, located in the SW SW NE, Section 17-32S-7W, Harper County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

Jac W. Carter

Subscribed and sworn to before me this 16th day of August, 1956.

Ruth W. Carter
 Notary Public

My Commission expires October 23, 1958.

PLUGGING
 FILE - SEC. 17 32 R 7W
 BOOK PAGE 89 LINE 40