


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-077-0103300-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Harper County, Sec. 18 Twp. 32S Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines 1650' FW, 1320' FN SE/4
Lease Owner Phillips Petroleum
Lease Name Yoder "A"
Office Address Box 779, Great Bend, Kansas Well No. 1
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-9-60 19
Application for plugging filed 6-7-60 19
Application for plugging approved 6-9-60 19
Plugging commenced 6-9-60 19
Plugging completed 6-9-60 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hemple
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 1490' to 210'. Set wood bridge plug at 210' and dumped 1/4 sx hulls. Dumped 15 sx cement to 168', mudded hole to 35' - set wood plug at 35', dumped 1/4 sx hulls and 10 sx cement in filling to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1960

CONSERVATION DIVISION

06-16-1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert Jones
Address Wichita, Kansas

STATE OF Kansas COUNTY OF Barton ss.
A. J. Willis (employee of owner) or ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. J. Willis*
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of June, 19 60

My commission expires 11-18-61 *Joseph P. Beal* Notary Public.

Phillips Petrol.

15-077-01033-00-00

EXPLORATION RECORD

18-32-7W

Lease Yoder "A"

Well 1

Formation Name	Top	Base	Remarks
Surface Clay	0	20	
Sand	20	40	
Red bed and shells	40	170	
Red bed	170	218	
Red bed	218	520	
Shale and shells	520	1255	
Anhydrite	1255	1290	
Anhydrite and lime	1290	1400	
Lime	1400	1750	
Shale and lime	1750	1900	
Shale and shells	1900	2020	
Shale and lime	2020	2095	
Lime	2095	2200	
Lime and shale	2200	3575	
Shale and shells	3575	3600	
Sand	3600	3715	
Shale and lime	3715	3940	
Lime	3940	4080	
Lime and shale	4080	4240	
Lime	4240	4295	
Shale and lime	4295	4490	
Lime	4490	4490	
TD			
FORMATION TOPS			
	Schlumberger		
Heetner	3294		
Toronto	3317		
Douglas	3403		
Stallmaker	3631		
Drum	3893		
Base LCO	4092		
Marmaton	4166		
Cherokee	4326		
Mississippi	4421		

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1960
06-16-1960
CONSERVATION DIVISION
Wichita, Kansas

Dry and abandoned