

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-079-20371-0001

API NUMBER ~~15-079-2037-00-01~~

LEASE NAME Smith #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 200' E SW SW SE

330
2110 Ft. from S Section Line

2110 Ft. from E Section Line

SEC. 23 TWP. 22 RGE. 2w (#) or (W)

COUNTY Harvey

Date Well Completed 8/8/78

Plugging Commenced 4/23/85

Plugging Completed 6/20/85

LEASE OPERATOR AMI, Inc.

ADDRESS Box 110, Moundridge, Ks. 67107

PHONE# (316) 345-6317 OPERATORS LICENSE NO. 5621

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is AC0-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	170'	none
				5 1/2"	3430'	1988'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pushed plug to 3000', sanded to 2900' & 6 sacks cement. Shot pipe at 2401', & 1988'

Pulled 55 joints of pipe. Plugged well with 200# hulls, 15 gel, 200# hulls, & 100 sacks 60/40 poz 2% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. JUN 24 1985


R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 85

Irene Hoover
Notary Public

My Commission Expires: 

DONALD J. MELLAND • GEOLOGIST

Phones: 241-1675 241-4582 • Box 783 • McPHERSON, KANSAS 67460

GEOLOGICAL REPORT

AMI, Inc.
Smith # 2
200'E SW SW SE, Sec. 23-22-2W
Field: Sperling South
Harvey County, Kansas

August 8, 1978
Elevation: 1456 KB, 1456 GL
Conn: 7/31/78; Comp: 8/7/78
Casing: 8-5/8" @ 170°/150ax.
5-1/2" @ 3430°/150ax.

FORMATION TOES

Lansing	2340	(-884)
Kansas City	2528	(-1072)
Mississippian	2950	(-1494)
Kimberhook	3268	(-1812)
Hunton	3289	(-1833)
Maquoketa	3334	(-1878)
Viola	3389	(-1933)
Simpson	3422	(-1966)
RTD	3435	(-1971)

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1985

CONSERVATION DIVISION
Wichita, Kansas

Cores: None

Drill Stem Tests: One test was taken in the Mississippian by Halliburton Services, job log attached.

Electrical Logs: None

Gas Detector: None

Measurements: Were taken from Kelly bushing, 5 feet above ground level.

FORMATION SUMMARY

KANSAS CITY

2650-2654 Limestone; buff, finely crystalline, oolitic, oolitic in part, poor to fair pinhole porosity, no shows of oil or gas, no odor.

If you need more information please let me know
Dug