

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY NESS SEC. 29 TWP. 17S RGE. 23W E/W  
Location as in quarters or footage from lines:  
C SW NE


Lease Owner KRM PETROLEUM CORP.  
Lease Name FOOS SUITE 300 Well No. 1-29X  
Office Address 1900 GRANT STREET, DENVER COLORADO 80203  
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE  
Date Well Completed 6-22-83  
Application for plugging filed July 5, 1983  
Plugging commenced 2:00 A.M. 6-22-83  
Plugging completed 4:45 A.M. 6-22-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Permission Obtained

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	537'	J-55	13 Jts.	

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Foos was plugged with 175 sks of 60/40 Paus 2% gel, 3% cc  
Plugs were staged at: 50 sks at 1680', 50 sks at 900',  
40 sks at 570', 10 sks at 40', 15 sks Rat Hole, 10 sks Mouse Hole.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton, Ness City

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
(employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Arnie Little ARNIE LITTLE  
P.O. Box 18611, Wichita, Ks. 67207  
(Address)

SUBSCRIBED AND SWORN TO before me this 5TH day of JULY, 19 83

Kathleen G. Quinn  
KATHLEEN G. QUINN Notary Public.

My Commission expires: MARCH 20, 1987



RECEIVED  
STATE CORPORATION COMMISSION

JUL 06 1983  
7-6-83  
CONSERVATION DIVISION  
Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD  
P.O. BOX 18611  
WICHITA, KANSAS 67207  
(316) 685-5372



W E L L L O G

15-135-22407-0000

WELL NAME: FOOS #1-29X

WELL LOCATION: 20' S of

Sec. 29-17S-23W

COMMENCED: 6-11-83 2:15 P.M.

COMPLETED: 6-22-83 4:15 A.M.

CASING RECORD: \_\_\_\_\_

8 5/8" set @ 537'

OPERATOR: KRM PETROLEUM CORP.

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

FORMATION:

FROM:

TO:

Greenclay-Gray Clays	0	566'
Clay & Shale	566'	920'
Red Bed	920'	1648'
Red Bed & Clay	1648'	2000'
Shales	2000'	2310'
Lime & Shale	2310'	3955'
Lime	3955'	4074'
Lime & Shale	4074'	4392'
Mississipian	4392'	4441'

RECEIVED  
STATE CONSERVATION COMMISSION

JUL 06 1983

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK) ss:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED  
20' S of Sec. 29-17S-23W, Ness County, Kansas TO THE BEST OF MY  
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

*Arnie Little*  
ARNIE LITTLE  
VICE-PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 5TH DAY OF JULY, 1983

MY APPOINTMENT EXPIRES MARCH 20, 1987

KATHLEEN G. QUINN  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appt. Exp. 3-20-87

*Kathleen G. Quinn*  
KATHLEEN G. QUINN  
NOTARY PUBLIC