


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 29 Twp. 17S Rge. 23 ~~XX~~ W (W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner DNB DRILLING, INC. & COMET PETROLEUM CO.

Lease Name Lynch 'A' Well No. 1

Office Address 737 First Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-22 19 69

Application for plugging filed 7-22 19 69

Application for plugging approved 7-22 19 69

Plugging commenced 7-22 19 69

Plugging completed 7-22 19 69

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surf.	288'	8-5/8"	288'	Left in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 660', plug, 70 sx cement,
Fluid to 270', plug, 20 sx cement,
Fluid to 40', plug, 10 sx cement,
Two sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas
7-28-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DNB DRILLING, INC.

Address 737 First National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF _____, ss.

James L. Donelson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
737 First Nat'l Bank Bldg., Wichita, Ks.
(Address)

Subscribed and Sworn to before me this 24th day of July, 19 69

Ella Priess
Notary Public.



15.135 10226 0000

DRILLERS' LOG

DNB DRILLING, INC.
and
COMET PETROLEUM COMPANY
737 First National Bank Building
Wichita, Kansas

Lynch 'A' #1
C SW NW, Sec. 29-17S-23W
Ness County, Kansas

Elevation: 2427 K.B.

Commenced: 7-12-69
Completed: 7-22-69

Surface Casing: 288' of
8-5/8" cemented w/150 sx
cement, 3% CC. 7-13-69

FORMATION

DEPTH

Surface Hole	288
Sand & Shale	1154
Shale	1718
Anhydrite	1754
Shale	2100
Shale & Lime	2784
Lime & Shale	3656
Shale & Lime	3836
Lime	4137
Lime & Shale	4428
Conglomerate	4445
Lime	4500' T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said State, this 24th day of July, 1969.

Ella Priess
Ella Priess, Notary Public

My Commission Expires:
August 25, 1972

