

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 28 Twp. 17S Rge. 23W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C NE NW

Lease Owner Icer Addis
Lease Name Anspaugh Well No. #1
Office Address P. O. Drawer 8038, Wichita, Kansas 67208
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole


Date Well completed April 15, 1978 19
Application for plugging filed April 15, 1978 19
Application for plugging approved April 15, 1978 19
Plugging commenced April 15, 1978 19
Plugging completed April 15, 1978 19

Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4452'
How depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
placed and the method or methods used in introducing it into the hold. If cement or other
materials were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows:
70 sacks @ 650', 20 sacks @ 240', 10 Sacks @ 40'. Plug down 12:00 p.m.,
April 15, 1978.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1978
5-18-78
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling Company


I, Kenneth J. Link of KANSAS COUNTY OF BARTON, ss.
(employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1978.

Loneita Barry
Loneita Barry Notary Public.

My commission expires March 28, 1980.



D R I L L E R S L O G

#1 Anspaugh

CASING RECORD: 7 jts. used 8-5/8" surface casing	COMPANY: Icer Addis	DESCRIPTION: C NE NW Section 28-17S-23W Ness County, Kansas
TOTAL ROTARY DEPTH: 4452'	CONTRACTOR: Strata Drilling Company	ELEVATION: 2391' GL
	COMMENCED: April 9, 1978	
	COMPLETED: April 15, 1978	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock and shale	0	305	Ran 287' used 8-5/8" surface casing; set and cemented @ 292' with 190 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 1:00 a.m., April 10, 1978.
Shale	305	1699	
Anhydrite	1699	1726	
Shale	1726	2870	
Lime and shale	2870	4452	

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 650', 20 sacks @ 240', 10 sacks @ 40'. Plug down @ 12:00 p.m., April 15, 1978.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1978

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link

Kenneth J. Link, President

Sworn to and subscribed before me this 20th day of April, 1978.

My commission expires 3-28-80.



Loneita Bafry

Loneita Bafry, Notary Public