

15135-19082-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 27 Twp. 17 Rge. 23W (E) (W)

Location as "NE/CNW&SW" or footage from lines C NW NW

Lease Owner Mull Drilling Co. Inc

Lease Name Ryan Well No. 1

Office Address 1625 Plaza Bldg. Wichita, 2 Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.

Date well completed 1/22/63 19

Application for plugging filed 1/22/63 19

Application for plugging approved 1/22/63 19

Plugging commenced 5:00 p.m. - 1/22/63 19

Plugging completed 11:00 p.m. - 1/22/63 19

Reason for abandonment of well or producing formation
Non productive.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4620' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled to within 400' of surface, with a plug and hulls and 25 sacks cement.
Hole then filled to within 40' of surface with a plug and hulls and 10 sacks cement.
Two sacks cement was put in rat hole plugging same.

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1963
2-5-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert and Jones Drilling Co.
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1963

My commission expires October 16, 1965 Notary Public.

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

15-135-19082-0000

RYAN #1
 C NW NW SECTION 27-17S-23W
 NESS COUNTY, KANSAS

COMMENCED: JANUARY 7, 1963
 COMPLETED: JANUARY 22, 1963

OPERATOR - MULL DRILLING Co., INC.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	910	SHALE	RAN 413.15' OF 8-5/8" CASING, SET @ 410' W/225 SACKS CEMENT.
910	1460	SHALE & SHELLS	
1460	1720	SHALE & RED ROCK	
1720	1740	ANHYDRITE	
1740	1940	SHALE & SHELLS	
1940	2545	SHALE & LIME	
2545	2715	LIME	
2715	2765	LIME & SHALE	
2765	2850	LIME	
2850	3210	LIME & SHALE	
3210	3230	LIME	
3230	3485	LIME & SHALE	
3485	3560	LIME	
3560	3725	LIME & SHALE	
3725	3755	LIME	
3755	3830	LIME CHALK	
3830	4465	LIME	
4465	4500	MISSISSIPPIAN	
4500	4518	LIME	
4518	4605	CHERT LIME	
4605	4620	LIME	
4820	TD		DRY & ABANDONED

State of Kansas
 FEB 5 1963
 COUNTY OF SEDGWICK

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C NW NW SECTION 27-17S-23W, NESS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 28TH DAY OF JANUARY, 1963, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963.

Vira A. McKenzie

 VIRA A. MCKENZIE, NOTARY PUBLIC