


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 33 Twp. 21 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner Chief Drilling Co., Inc.
Lease Name Webb Well No. 1
Office Address Ferrell Building, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed February 24, 19 57
Application for plugging filed February 24, 19 57
Application for plugging approved February 24, 19 57
Plugging commenced February 24, 19 57
Plugging completed February 24, 19 57
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russell Brundage, Hoisington, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	988'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set wooden plug at 420', run 1/2 sack hulls and 20 sacks cement on top of plug. Set wooden plug at 20', ran 1/2 sack hulls and 5 sacks cement. Job completed 2:30 P.M. February 24, 1957.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor company
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover, Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
CHIEF DRILLING CO., INC. (Signature) V. Richard Hoover Pres.
Ferrell Building, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 57

My commission expires August 29, 1959

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 33 T. 21 R. 16 W
BOOK PAGE 143 LI E 31

FEB 27 1957
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Chief Drilling Co., Inc.
Ferrell Building
Great Bend, Kansas

Elevation: 1993 D.F.
1995 K.B.

NO. 1 WEBB
SE SW SE Sec. 33-21-16W
Pawnee County, Kansas

Commenced: 2/7/57
Completed: 2/25/57

DRY AND ABANDONED

Contractor: Chief Drilling Co., Inc.
Rotary: 0 - 3880' f.d.

Casing Record: 987.91' - 8 5/8" used 28# casing, set with 450
sacks at 985'; cement circulated.

Figures Indicate Bottoms of Formations.

Formation Tops & Datums

Sand	0 -	50
Clay	50 -	70
Shale	70 -	420
Sand	420 -	530
Shale and Shells	530 -	800
Red Bed and Shale	800 -	980
Anhydrite	980 -	1010
Shale and Shells	1010 -	1810
Shale and Lime	1810 -	2010
Lime and Shale	2010 -	2490
Shale and Lime	2490 -	2825
Lime and Shale	2825 -	3220
Lime	3220 -	3805
Lime and Conglomerate	3805 -	3848
Dolomite	3848 -	3880' t.d.

Heebner	3405	(-1410)
Brown Lime	3507	(-1512)
Lansing	3516	(-1521)
Base Kansas City	3757	(-1762)
Marmaton	3770	(-1775)
Conglomerate	3809	(-1814)
Arbuckle	3845	(-1850)
Total Depth	3880	(-1885)

State of Kansas)
County of Barton)

I hereby certify that the above is a true and correct copy of
Drillers Log of well drilled in the SE SW SE Sec. 33-21-16W, Pawnee
County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 25th day of February,
1957.

Emma Jean Sayre
Emma Jean Sayre, Notary Public

My commission expires:
August 29, 1959.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1957

PLUGGING
FILE SEC. 33 T. 21 R. 16 W.
BOOK PAGE 143 LINE 31

CONSERVATION DIVISION
Wichita, Kansas