

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 12 Twp. 18S Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines SE NE NE
Lease Owner Four-Way Operating, Inc.
Lease Name Elmore Well No. 3
Office Address P. O. Box 698, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 27 19 72
Application for plugging filed July 27 19 72
Application for plugging approved July 27 19 72
Plugging commenced July 27 19 72
Plugging completed July 27 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	335.69'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Plugged hole as follows: Plugged at 465' with 50 sacks of regular cement; plugged at 300' with 25 sacks of common cement; plugged at 40' with 10 sacks of regular cement. Plug down at 5:10 P. M. July 27, 1972.

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1972
7-31-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 28th day of July, 19 72

My commission expires December 14, 1973

Elaine H. Taylor
Elaine H. Taylor Notary Public.



JUL 31 1972

CONSERVATION DIVISION
Wichita, Kansas

D R I L L E R S L O G

#3 Elmore

CASING RECORD:
329.69' of used 8-5/8"
surface casing.

COMPANY: Four-Way Operating, Inc.

DESCRIPTION: SE NE NE
Section 12-18S-21W
Ness County, Kansas

TOTAL DEPTH:
4200'

COMMENCED: July 18, 1972

ELEVATION: 2158' RB

COMPLETED: July 27, 1972

D. & A.

15135.20648.0000

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Shale & Sand	0	364	Ran 329.69' of used 8-5/8" surface casing; set and cemented at 335.69' with 170 sacks of common cement, 2% gel and 3% C. C. Plug down at 1:35 A. M. July 19, 1972.
Shale w/Sand Streaks	364	470	
Shale, Sand & Red Bed	470	792	
Dakota Sand	792	1077	
Red Bed	1077	1132	
Red Bed, Sand & Shale	1132	1387	
Anhydrite	1387	1417	
Shale & Shells	1417	1708	
Shells, Shale & Broken Lime	1708	2123	
Shale & Lime	2123	2423	
Lime, Shale w/Broken Lime	2423	2585	
Shale & Lime	2585	2911	
Shale, Lime w/Broken Lime	2911	3107	
Lime & Shale	3107	4050	
Lime	4050	4106	
Lime & Shale	4106	4112	
Lime	4112	4119	
Sand & Shale	4119	4124	
Lime	4124	4200	

ROTARY TOTAL DEPTH 4200'

D. & A.

Plugged hole as follows: Plugged at 465' with 50 sacks of regular cement; plugged at 300' with 25 sacks of common cement; plugged at 40' with 10 sacks of regular cement. Plug down at 5:10 P. M. July 27, 1972.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

My Commission Expires:
December 14, 1973



Subscribed and sworn to before me this 28th day of July, 1972.

Elaine H. Taylor
Elaine H. Taylor, Notary Public