

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County. Sec. 12 Twp. 18 Rge. 21 (E) (W) X

Location as "NE/CNW&SWK" or footage from lines NE/-SE-NE

Lease Owner R. W. Shields

Lease Name Elmore Well No. 2

Office Address 666 Fourth Natl. Bank Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 16 1960

Application for plugging filed August 10, 1964

Application for plugging approved July 24, 1964


Plugging commenced July 24, 1964

Plugging completed July 24, 1964

Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production May 2, 1963

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Cherokee Sand Depth to top 4,092 Bottom 4,114 Total Depth of Well 4,185 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface sands	water	0	50	8 5/8"	252'	none
Mississippi Line	water	4,153	4,185	5 3/4"	4,183'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton spotted 20 sacks cement through 2 1/2 inch tubing at 566 feet, pulled tubing to 248 feet and spotted 20 sacks cement, pulled tubing to 30 feet and spotted 10 sacks cement. Hole was filled with heavy mud between each cement stage. Bradenhead was squeezed with 50 sacks cement after finishing plugging casing.

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1964
8-11-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prairie Oilfield Service, Inc.

Address Box 797, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold

Box 797, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of August, 1964

My commission expires Jan. 26, 1967

Carroll S. Cook
Notary Public.

WELL LOG

15735 00551 0000

R.W. Shields
308 Rule Building
Wichita, Kansas

Elmore #2
NE SE NE of Sec. 12-18S-21W
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.
Estary: 0 - 4185

Commenced: 4-5-60
Completed: 4-16-60

Casing Record: (8 5/8" set @ 252' with 175 Sacks Cement, Cement circulated.
5 1/2" set @ 4183' with 100 Sacks Cement.)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Clay & Sand	0	252	2143 Gr.
Shale & Shells	252	330	2145 D.F.
Sand & Shale	330	365	2148 K.B.
Shale, Shells & Red Bed	365	800	
Sand	800	1080	
Shale & Shells	1080	1260	
Shale w/sand Streaks	1260	1372	
Anhydrite	1372	1400	Anhydrite 1372 (+ 776)
Shale & Shells	1400	2085	Hoebner 3478 (-1330)
Shale & Lime	2085	2355	Lansing 3623 (-1475)
Lime	2355	2465	Cherokee Shale 4062 (-1914)
Lime & Shale	2465	2940	Cherokee Sand 4092 (-1944)
Lime	2940	3010	Mississippi 4153 (-2005)
Shale & Lime	3010	3600	
Lime	3600	4062	
Shale	4062	4070	
Lime	4070	4092	
Sand	4092	4104	
Shale & Sand	4104	4153	
Chert	4153	4185	
Total Depth	4185		

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
 SS
COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE SE NE of Section 12-18S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING COMPANY, INC.
V. Richard Hoover
V. Richard Hoover - President

Subscribed and sworn to before me this 23rd day of April, 1960.

Morris Taylor
Morris Taylor, Notary Public

My commission expires: May 19, 1962.