

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas


WELL PLUGGING RECORD

Ness County, Sec. 12 Twp. 18 Rge. 21 (E) (W) X
Location as "NE/CNW%SW%" or footage from lines NE NE NE

Lease Owner James W. Rockhold
Lease Name Elmore Well No. 1
Office Address P. O. Box 698 Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 10-22-69 19____
Application for plugging approved 10-23-69 19____
Plugging commenced 11-13-69 19____
Plugging completed 11-13-69 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	268	None
				5 1/2	None	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Allied Cementing Company, Inc. squeezed well with 4 sacks of hulls, 35 sacks of mud and 75 sacks of 50/50 pozmix 6% gel. Finished with 1000 psi.


RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)



Subscribed and Sworn to before me this 24 day of November, 19 69
Glen D. [Signature]
Notary Public.

DRILLERS' LOG

Well Owner: R. W. Shields
 Farm Name: Elmore Well No. 1
 Commenced: 7/10/58
 Completed: 7/27/58
 Total Depth: 4625'
 Casing: 8 5/8" @ 268' cemented *4/200 sacks*
 5 1/2" @ 4238' cemented *4/125 sacks*

NE NE NE
 Sec. 12-18S-21W
 Ness County, Kansas

Elevation:
 Production:

Contractor: Peel Brothers, Inc.

Figures below indicate bottoms of formations:

Surface clay	0	15
Clay and shale		268
Shale and sand		580
Shale		760
Sand		1070
Shale and red bed		1260
Shale and sand		1315
Shale		1390
Gyp		1400
Anhydrite		1440
Shale		1645
Shale and shells		1845
Sand and shale		2055
Shale and lime		2375
Lime		2480
Shale and lime		2895
Lime		3080
Shale and lime		3290
Lime		3445
Lime and shale		3535
Lime		3975
Lime and shale		4050
Lime		4108
Lime and shale		4129
Sand, lime and shale		4147
Lime		4210
Lime and chert		4255
Lime		4330
Lime and shale		4365
Lime		4625
Total Depth		4625

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 31 1969
 CONSERVATION DIVISION
 Wichita, Kansas

The above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY *Wendell G. Peal*

SUBSCRIBED AND SWORN to before me this 29th day of July, 1958

My commission expires: April 27, 1960

Luck Grant
 Notary Public