

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
10-27-03
OCT 27 2003
KCC WICHITA

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-22-03 (Date)
by: Richard Lacy (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cherokee Depth to Top: 4221' Bottom: 4288' T.D. 4300'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-22188-00-00
Lease Name: Mantz
Well Number: 2
Spot Location (OOQQ): NE - SW - NW -
1650 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 9 Twp. 18 S. R. 21 East West
County: Ness
Date Well Completed: 2-28-82
Plugging Commenced: 10-22-03
Plugging Completed: 10-22-03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cherokee	oil/water	4224'	4228'	8 5/8	288	None
				4 1/2	4296'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Mixed & pumped 20 sacks cement with 200# of hulls down casing and displaced to perfs (4224-28'), shut in with 600 psi.
Perforate @ 700', mix & pump 120 sacks with 100# of hulls down casing, pump 15 sacks down 8 5/8 braden head and pressure up to 500 psi, top off 4 1/2 casing with 15 sacks, well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: Ness City, KS 67560
Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Ness ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 23rd day of October, 20 03

Bernice Moore My Commission Expires: 2/7/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

