

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22,912-0000

LEASE NAME Arnold

WELL NUMBER 1-31

330 Ft. from S Section Line

4460 Ft. from E Section Line  
Irregular Section

SEC. 31 TWP. 16S RGE. 26 ~~NE~~ or (W)

COUNTY Ness

Date Well Completed 9-9-85

Plugging Commenced 8-30-85

Plugging Completed 3 pm, 9-9-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Agate Petroleum, Inc.

ADDRESS 1301 Fourth National Bank Bldg., Tulsa, OK 74119

PHONE#( 918 ) 585-9016 OPERATORS LICENSE NO. 4459

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation none Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	salt water	4580	96	8-5/8"	423'	none
Lansing	salt water	4210	40			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
4650-2060': 9.2 ppg mud; 2060-1872': 50 sx 60-40 pozmix w/3% gel, 2% CC, 9.2 mud; 1250-1063': 50 sx. 60-40 pozmix w/3% gel, 2% CC, 9.2 mud; 1000-869': 35 sx. 60-40 pozmix, 3% gel, 2% CC, 9.2 mud; 480-297': 50 sx. 60-40 pozmix, 3% gel, 2% CC, 9.2 mud; 40-0': 15 sx. 60-40 pozmix, 3% gel, 2% CC. 15 sx cement in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sage Drilling Co., Inc. License No. 5421

Address 202 S. St. Francis, Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Charles Casey Coats, P.E. Agent for Operator  
(~~XXXXXXXXXXXXXXXXXXXX~~) or (~~XXXXXXXX~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Casey Coats, P.E.

(Address) Charles Casey Coats, P.E.  
202 S. St. Francis, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 10 day of September, 19 85



Sandra Kay Woosypiti  
Notary Public  
Sandra Kay Woosypiti

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1985  
9-11-85  
CONSERVATION DIVISION