

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22,845 - (GUR)

LEASE NAME ARNOLD

WELL NUMBER 2-31

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3630 Ft. from S Section Line

3630 Ft. from E Section Line

LEASE OPERATOR Agate Petroleum, Inc.

SEC. 31 TWP. 16S RGE. 26 (S) or (W)

ADDRESS 1301 Fourth National Bldg., Tulsa, OK 74119.

COUNTY Ness

PHONE#(918) 585-9016 OPERATORS LICENSE NO. 4459

Date Well Completed 11-10-85

Character of Well D&A

Plugging Commenced 11-9-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-10-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? no-late night <sup>weekend</sup>

Which KCC/KDHE Joint Office did you notify? Dodge City - recommendation on Drilling Intent

Is ACO-1 filed? yes if not, is well log attached? well log is attached

Producing Formation none Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	salt water	4219	50	8-5/8	403	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
4670-2060: 9.1 ppg mud; 2060-1872': 50 sx 60-40 poz, 2% gel, 3% CC, 9.1 ppg mud; 1250-1063': 50 sx, 60-40 poz, 2% gel, 3% CC, 9.1 ppg mud; 1000-869': 35 sx, 60-40 poz, 2% gel, 3% CC, 9.1 ppg mud; 450-267': 50 sx 60-40 poz, 2% gel, 3% CC, 9.1 ppg mud; 40-0': 15 sx, 60-40 poz, 2% gel 3% CC; 15 sx cement in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sage Drilling Co., Inc. License No. 5421

Address 202 S. St. Francis, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Charles Casey Coats, P.E. Agent for (Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Casey Coats, P.E.

(Address) 202 S. St. Francis, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 11 day of November, 19 85

My Commission Expires: June 5, 1988 Notary Public  
Sandra Kay Woosypiti

RECEIVED  
STATE CORPORATION COMMISSION

11-12-85  
NOV 12 1985

Form CP-4  
Revised 08-84