

15.135.22292.0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ness SEC. 31 TWP. 16 RGE. 26 E/W
 Location as in quarters or footage from lines:
 SW 1/4 1650' FSL 990' FWL

Lease Owner R & D Petroleum
 Lease Name Arnold Well No. #1
 Office Address Box 298 Hoisington, Kansas 676544
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 10-26-82
 Application for plugging filed 10-26-82
 Plugging commenced 8:00 am 10-26-82
 Plugging completed 10:00 am 10-26-82

Locate Well
 correctly on above
 Section Platt.

Reason for abandonment of well or producing formation
Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 4640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Filled hole to 1220' with heavy mud and mixed 70 sacks of cement and pumped in hole thru
 drill pipe.

Filled hole to 270' with heavy mud and mixed 40 sacks of cement and pumped in hole thru
 drill pipe.

Filled hole to 40' built solid bridge pushed down plug and mixed 10 sacks and filled hole
 to the bottom of the cellar; mixed 10 sacks and pumped into the rat hole.


All cement used was 50-50 Poz Mix 4 % Gel 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revlin Drlg., Inc.

STATE OF Kansas COUNTY OF Russell, ss.

Stanley C. Lingreen (employee of owner) or ~~(owner or operator)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen
Box 293 Russell, Kansas 67665
 (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 82

RECEIVED
 STATE OF KANSAS
 Notary Public.

My Commission expires: November 10, 1984

NOV 2 1982
 11-2-82
 CONSERVATION DIVISION
 Wichita, Kansas