

15135-21867-0000

RECEIVED

STATE OF KANSAS
STATE CORPORATION COMMISSION

AUG 23 1980
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

PALOMINO
PETROLEUM Ness County. Sec. 31 Twp. 16S Rge. 26W E/W

Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW SW SE

Lease Owner Palomino Petroleum

Lease Name Hagstrom Well No. #1

Office Address 500 Insurance Building, Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed August 18, 1980 19

Application for plugging filed August 18, 1980 19

Application for plugging approved August 18, 1980 19

Plugging commenced August 18, 1980 19

Plugging completed August 18, 1980 19

Reason for abandonment of well or producing formation dry hole


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4600'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:
60 sacks @ 900', 30 sacks @ 260', hulls and 10 sacks @ 40', 5 sacks in rathole. Plugging completed at 4:00 p.m., August 18, 1980.

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss. Charles W. Steincamp (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1980.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-84.



RECEIVED

AUG 23 1980

PALOMINO
PETROLEUM

15-135-21864-0000

D R I L L E R S L O G

#1 Hagstrom

CASING RECORD:
7 jts. new 20#
8-5/8" surface
casing

COMPANY: Palomino Petroleum
CONTRACTOR: Strata Drilling Company
COMMENCED: August 11, 1980
COMPLETED: August 18, 1980

DESCRIPTION: SW SW SE
Section 31-16S-26W
Ness County, Kansas
ELEVATION: 2628' KB

TOTAL ROTARY
DEPTH: 4600'

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale, sand	0	295	Ran 285' new 20# 8-5/8" surface casing; set and cemented with 180 sacks common, 2% gel, 3% C.C. at 290'. Cement circulated. Plug down at 7:15 p.m., August 12, 1980.
Shale, sand	295	2030	
Anhydrite	2030	2063	
Shale	2063	2620	
Lime and shale	2620	4560	
Lime	4560	4600	Ran 1 drill stem test
			Ran 1 electric log.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 60 sacks @ 900', 30 sacks @ 260', hulls and 10 sacks at 40', 5 sacks in rathole. Plugging completed at 4:00 p.m., August 18, 1980.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1980
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 22nd day of August, 1980.

My appointment expires 3-28-84.

Loneita Barry
Loneita Barry, Notary Public

