

API NUMBER 15135704360000

LEASE NAME Arnold

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 16 RGE. 26 COR(W)

COUNTY Ness

Date Well Completed 5-20-71

Plugging Commenced 4-8-92

Plugging Completed 11:30 AM

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS Box 97, Ellinwood, Kansas 67526

PHONE# (816) 564-2577 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-8-92 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? NA

Producing Formation Depth to Top 4008 Bottom 4158 T.D. 4562

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	288	0
				5 1/2	4554	505

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Spot 50 sx 60/40 w/6% gel down 5 1/2 casing to 1220 ft, 50 sx cement at 500 ft, 40 sx cement at 300 ft (it circulated), pulled casing & topped off w/10 sx cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Anna K. Burke (Employee of Operator (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Anna K. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 9 day of April, 19 92



Gary G. Burke
 Notary Public

