

15735-20504-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 30 Twp. 16S Rge. XXX26 (W)
Location as "NE/CNWKSW" or footage from lines SE SE SW
Lease Owner Pickrell Drilling Company
Lease Name Jennings "B" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 2 19 71
Application for plugging filed November 2 19 71
Application for plugging approved November 2 19 71
Plugging commenced November 2 19 71
Plugging completed November 2 19 71
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo F. Massy
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 720' w/70 sacks cement, plug @ 240' w/20 sacks,
Top Plug @ 40' w/10 sacks.


RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1971
CONSERVATION DIVISION
Wichita, Kansas
11-15-71

Name of Plugging Contractor Pickrell (If additional description is necessary, use BACK of this sheet)
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1971



Esther Lamone
Notary Public.

My commission expires January 19, 1973

ROTARY DRILLING LOG

15-135-20504-0002

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 10/22/71

Rotary Drilling Completed 11/2/71

LOCATION: Jennings "B" No. 1, SE SE SW Sec. 30-16S-26W,
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 7 Jts. 8-5/8" surface casing set @ 237' KB. Cemented with 140 sacks. Completed 4:45 P.M. Circulated.

No oil string run. D & A, Plugged 12:00 Midnight, November 2, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

95	Surface Soil - Clay	<u>C.F.S.</u>
160	Shale - Clay	3945
240	Shale	4070
1190	Shale w/sand streaks	4158
1481	Shale - Red Beds	4185
1510	Blain	4225
1575	Red Beds	4250
1880	Sand	4255
2087	Shale	4290
2117	Anhydrite	4512
2470	Shale	4575
2690	Lime & Shale	4585
3590	Lime	4592
3930	Lime & Shale	4602
4485	Lime	4615
4512	Lime & Shale	4625
4574	Lime	
4592	Lime & Chert	
4625	Chert & Lime, RTD	

Slope Tests

2000
2500
3000
3500
4000
4500

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 8th day of November, 19 71, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

[Signature]
Esther Lamone Notary Public

