


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

15-755-214130000
WELL PLUGGING RECORD

Ness County, Sec. 35 Twp. 16S Rge. (E) 26 (W)
Location as "NE/CNWxSWx" or footage from lines. C SE NE
Lease Owner Chief Drilling Co., Inc.
Lease Name Hopkins Well No. #1
Office Address 905 Century Plaza, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 25, 1978 19
Application for plugging filed Jan. 27, 1978 19
Application for plugging approved Jan. 27, 1978 19
Plugging commenced Jan. 25, 1978 19
Plugging completed Jan. 25, 1978 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4580 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	271'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 1500' w/70 sx. cement
Plugged through drill pipe @ 240' w/20 sx. "
Plugged through drill pipe @ 40' w/10 sx. "

RECEIVED
STATE CORPORATION COMMISSION
FEB 01 1978
2-1-78
D.V. STUBBINS
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of January, 1978

Marilyn Sinard
Marilyn Sinard Notary Public.

My commission expires _____

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

WELL LOG

15 BS 21413 0000

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 HOPKINS
C SE NE Sec. 35-16S-26W
Ness County, Kansas

CONTRACTOR: Warrior Drilling, Inc.
CASING RECORD: 8 5/8" @ 271' w/200 sx.

COMMENCED: January 17, 1978
COMPLETED: January 25, 1978

FORMATION	FROM	TO	ELEVATIONS
Surface Sand	0	281	2600 Gr.
Sand & Shale	281	1901	2602 D.F.
Shale	1901	1974	2605 K.B.
Anhydrite	1975	2006	
Shale	2007	4098	
Shale & Lime	4098	4422	
Lime	4422	4580	
Total Depth	4580		

FORMATION TOPS	
Anhydrite	1974 + 631
Base Anhy.	2006 + 599
Heebner	3871 - 1266
Lansing	3916 - 1311
BKC	4216 - 1611
Ft. Scott	4422 - 1817
Miss.	4524 - 1919
RTD	4580 - 1975

D & A

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SE NE of Sec. 35-16S-26W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 31st day of January, 1978.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard, Notary Public