

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-135-21580-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 34 Twp. 16S Rge. 26 NE/W
Location as "NE/CNW/SW" or footage from lines
C NE SW

Lease Owner Sidwell Oil & Gas Co.
Lease Name Dumler Well No. 1
Office Address Box 2475, Pampa, Tx. 79065
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole


Date Well completed 2-5 1979
Application for plugging filed 2-5 1979
Application for plugging approved 2-5 1979
Plugging commenced 2-5 1979
Plugging completed 2-5 1979

Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production
-- 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4555
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	348'	8-5/8"	348'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to feet to
feet for each plug set.

Fluid to 720', plug, 70 sx
Fluid to 300', plug, 20 sx
Fluid to 40', plug, 19 sx

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1979
2-12-79
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description necessary, use BACK of this sheet)

Name of Plugging Contractor D & B DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
Suite 515 R.H. Garvey Bldg., Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 5th day of February, 1979

My commission expires April 30, 1979

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLER'S LOG

15:135-2158'0-0000

SIDWELL OIL & GAS CO.
No. 1 Dumlir
C NE SW Sec. 34-16S-26W
Ness Co., Ks.

Commenced: 1-24-79
Completed: 2-5-79

Surface Casing: 340' of 8-5/8"
cemented w/200 sx, 2% gel, 3% cc
1-25-79

FORMATION

DEPTH

Surface Hole	0 - 348
Shale	348 - 1404
Blaine	1404 - 1412
Sand & Shale	1412 - 1520
Lime & Sand	1520 - 1980
Shale & Lime	1980 - 2310
Lime & Shale	2310 - 3780
Lime	3780 - 4230
Shale	4230 - 4372
Lime	4372 - 4435
Shale	4435 - 4525
Lime	4525 - 4555 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 5th day of February, 1979.

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1979

CONSERVATION DIVISION
Wichita, Kansas

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedwick County, Kansas
My Appt. Exp. April 30, 1979