


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 34 Twp. 16S Rge 26W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C SE NE

Lease Owner PUBLISHERS PETROLEUM
Lease Name Dumler Well No. 1
Office Address P.O. Box 25125, Okla. City, Ok. 73125
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 4-28 19 76
Application for plugging filed 8-28 1976
Application for plugging approved 4-28 1976
Plugging commenced 4-28 1976
Plugging completed 4-28 1976
Reason for abandonment of well or producing formation
No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4600
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	FOOT IN	PULLED OUT
Surface Hole	Shale	Surf	286	8-5/8"	279	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

MAY 03 1976

Fluid to 720', plug, 70 sx cement: 5-3-76
Fluid to 240', plug, 20' sx cement: CONSERVATION DIVISION
Fluid to 40, plug, 1/2 sx hulls, 10 sx cement: Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
7-1 First Nat'l Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April 19 76

My commission expires 8-25-76

Ella Priess
Notary Public.

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

15-135-21191-0000

PUBLISHERS PETROLEUM
P. O. Box 25125
Oklahoma City, Okla. 73125

Dumler #1
C SE NE, Sec. 34-16S-26W
Ness County, Kansas

Elev: 2621 K.B.

Commenced: 4-19-76
Completed: 4-28-76

Surface Casing: 279' of 8-5/8"
cemented w/200 sx common cement,
2% Gel, 3% cc. 4-20-76

FORMATION

DEPTH

Surface Hole	0 - 286
Shale	286 - 655
Shale, Sand, Red Bed	655 - 1405
Shale	1405 - 1420
Blaine Anhydrite	1420 - 1430
Shale	1430 - 1500
Sand	1500 - 1745
Shale	1745 - 2006
Anhydrite	2006 - 2175
Shale	2175 - 2511
Lime & Shale	2511 - 2745
Lime	2745 - 2990
Shale & Lime	2990 - 3265
Lime	3265 - 3505
Lime & Shale	3505 - 3695
Lime	3695 - 4600 RTD.

APR 28 1976
Notary Public

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 29th day of April, 1976.

Ella Priess

Ella Priess, Notary Public

<i>Ella Priess</i>
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976