


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County: Sec. 34 Twp. 16S Rge. XXV 26 (W)
Location as "NE/CNWxSWx" or footage from lines C SW SE
Lease Owner Pickrell Drilling Company
Lease Name Dumler "L-M" Unit Well No. 4
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 22 1972
Application for plugging filed March 22 1972
Application for plugging approved March 22 1972
Plugging commenced March 22 1972
Plugging completed March 22 1972
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4545 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 720' w/70 sacks, Middle Plug @ 240' w/20 sacks,
Top Plug @ 40' w/10 sacks.




(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 24th day of March, 1972

Esther Lamone
Notary Public.

ROTARY DRILLING LOG

15735 20586 0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 3/12/72

Rotary Drilling Completed 3/22/72

LOCATION: Dumler "L-M" Unit No. 4, C SW SE Section 34-16S-26W
Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Run 7 Jts. 8-5/8" surface casing set @ 253' KB. Cemented w/150
sacks. Completed 6:15 P.M. Circulated.

No oil string run. D & A, Plugged down 8:00 P.M. March 22, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40 Clay Post Rock
1465 Shale
1710 Sand
1975 Shale
2008 Anhydrite
2325 Shale
2600 Shale & Lime Stringers
2820 Shale & Lime
2980 Lime
3350 Shale & Lime
3502 Lime & Shale
3695 Shale & Lime
3860 Sandy Lime & Shale
3935 Shale & Lime
3985 Lime
4060 Lime & Shale
4195 Lime
4274 Lime & Shale
4298 Lime
4358 Lime & Shale
4525 Lime
4545 Mississippi, RTD

C.F.S.

4270
4289
4427
4500
4515
4525
4545

S.L.M.

Board 4289.40
Strap 4288.52

.88 Difference

Slope Tests

2000
2500
3000
3500
4000
4500

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS
COUNTY OF SEDGWICK } ss.:

On this 24th day of March, 1972, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Notary Public