

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ness County, Sec. 33 Twp. 16S Rge. XX-26 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Riese "A" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 9 1972  
Application for plugging filed May 9 1972  
Application for plugging approved May 9 1972  
Plugging commenced May 9 1972  
Plugging completed May 9 1972  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4591 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 720' w/70 sacks, Middle Plug @ 240' w/20 sacks,  
Top Plug @ 40' w/10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1972  
5-17-72  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 12th day of May, 1972

January 19, 1973  
Esther Lamone  
Notary Public.



ROTARY DRILLING LOG

15.135.20660.0000

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 4/26/72

Rotary Drilling Completed 5/9/72

LOCATION: Riese "A" No. 1, C NE SE Sec. 33-16S-26W  
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 265' KB. Cemented with  
150 sacks. Completed 2:15 P.M. Circulated.

No oil string run. D & A, Plugged 11:45 P.M. May 9, 1972

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

30	Surface Soil - Post Rock	C.F.S.	
65	Sand	3925	4467
268	Shale & Shells	3950	4535
268	Cement	3985	4550
380	Shale & Shells	4025	4571
1570	Shale	4038	4581
1785	Sand	4050	4591
2033	Shale	4177	
2068	Anhydrite	4245	
2310	Shale	4335	
2670	Shale & Lime		
2725	Shale		
2843	Lime - Shale		
3410	Shale & Lime		
3615	Shale		
3730	Lime & Shale		
3805	Shale & Lime		
3915	Lime & Shale		
3980	Shale & Lime		
4025	Lime & Shale		
4478	LIME		<u>Slope Tests</u>
4530	Lime & Shale		2000
4545	Lime & Chert		2500
4591	Miss., RTD		3000
			3500
			4000
			4500

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. SEBITTS Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 12th day of May, 1972, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

[Signature]  
Esther Lamone Notary Public

