

API NUMBER 15-077-20345-00-00

LEASE NAME Maddux

RECEIVED
 09-10-2001
 SEP 10 2001

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 33 TWP. 33S RGE. 6 (E) or (W)

COUNTY Harper

Date Well Completed 03/31/1976

Plugging Commenced 08/29/2001

Plugging Completed 08/30/2001

LEASE OPERATOR KCC WICHITA Stelbar Oil Corporation, Inc.

ADDRESS 155 North Market, Suite #500; Wichita, KS 67202

PHONE# (316) 264-8378 OPERATORS LICENSE NO. 6044

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08/28/01 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4462' Bottom 4530' T.D. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Oil & Gas	Surf.	224'	8-5/8"	224'	None
4462'-4530'		Surf.	4547'	4 1/2"	4547'	1124'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Set CIBP @ 4460'; dump 2 sacks cement on plug. Shoot off casing @ 1124'; spot 35 sx cement @ 734'; circulate 127 sx cement from 290' to surface. Cut off casing head.

Name of Plugging Contractor Stelbar Oil Corporation, Inc. License No. 6044

Address 155 N. Market, Suite #500; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Stelbar Oil Corporation, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Roscoe L. Mendenhall, Petroleum Engineer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Roscoe L. Mendenhall

(Address) 155 N. Market, #500
 Wichita, KS 67202

NANCY N. PRUITT
 Notary Public - State of Kansas
 My Appt. Expires 06-11-05

SUBSCRIBED AND SWORN TO before me this 7th day of September, 2001

Nancy N. Pruitt
 Notary Public - Nancy N. Pruitt

My Commission Expires: June 11, 2005

USE ONLY ONE SIDE OF EACH FORM