

API NUMBER 15-077-21-265-00-00

LEASE NAME Carothers

WELL NUMBER 1

4,620 Ft. from S Section Line

3,300 Ft. from E Section Line

SEC. 11 TWP. 33S RGE. 6 ~~W~~ or (W)

COUNTY Harper

Date Well Completed 1/93

Plugging Commenced 7/25/94

Plugging Completed 7/29/94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Boswell Energy Corporation

ADDRESS 501 W. I-44, Suite 300, Okla City, OK 73118

PHONE# (405) 840-4073 OPERATORS LICENSE NO. 4538

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 8, 1994 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? log furnished w/ ACO-1

Producing Formation Mississippi Depth to Top 4,370 Bottom 4,630 T.D. 5,040

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Stalnaker	Water	3520	3584	8 5/8	219	none
Cherokee	Water	4182	4229	5 1/2	4836	3006
Mississippi	Gas & Water	4320	4630			
Viola	Water	4785	4810			
Arbuckle	Water	4966				

Describe in detail the manner in which the well was plugged, indicating where the mud fill was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Set CIBP @ 4320', 2 sx cem on top. Pull casing to 1062'. Spot 35' sx plug. Pull casing to 710' spot 35' sx plug. Pull casing to 280' cir 115' sx to surface after cement fall back. Refill w/ 3 yrd. ready mix. Hole kept full of mud while pull casing. Cut 8 5/8 off 7' below G.L. - weld on cap.

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P.O. Box 781624, Wichita, KS 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Boswell Energy Corporation

STATE OF Oklahoma COUNTY OF Oklahoma

R.P. Brandenburg (Employee of Operator or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described well, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) R.P. Brandenburg

(Address) 501 W. I-44, Suite 300
 Oklahoma City, OK 73118

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 94

Notary Public

My Commission Expires: MY COMMISSION EXPIRES 2-3-98

USE ONLY ONE SIDE OF EACH FORM

KCC RECEIVED #2
 AUG 11 1994
 WICHITA, KS

RECEIVED
 CORPORATION COMMISSION
 08-11-1994
 AUG 11 1994

CONSERVATION DIVISION
 WICHITA, KS

