

LEASE NAME Williams

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-5

1000 Ft. from S Section Line

3830 Ft. from E Section Line

SEC. 5 TWP. 33 SRGE. 6 (E) or (W)

COUNTY Harper

LEASE OPERATOR MESSENGER PETROLEUM, INC.

ADDRESS 1015 E. Hwy 54, Kingman, KS 67068

PHONE# (316) 532-5400 OPERATORS LICENSE NO. 4706

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 1-16-91

Plugging Commenced 10-05-95

Plugging Completed 10-07-95

The plugging proposal was approved on 9-19-95 (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4420 Bottom 4425 T.D. 5100

Show depth and thickness of all water, oil and gas formations. P.B.T.D. 4652

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Gas	surface	261	8 5/8	261	-----None-----
		surface	4675	4 1/2	4675	3309

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 10-5-95: dump 205 gal sand, 10-6-95: sand bridged off @ 1500', circulate bridge out of hole (100') (approx. 65 gal sand) - perf's plugged off because we were able to circulate, tag bottom @ 4520, apparently some sand still falling, set wire line plug @ 4350, dump 2 sx cement on top of plug, 10-7-95: Allied spot 35 sx @ 1287.73',
(If additional description is necessary, use BACK of this form.) (continued on back)

Name of Plugging Contractor Shawnee License No. 30346

Address 611 N. Blaine, Attica, KS 316-254-7893

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MESSENGER PETROLEUM, INC.

STATE OF KANSAS COUNTY OF Kingman, ss.

Jon F. Messenger (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as shown that the same are true and correct, so help me God.

(Signature) Jon F. Messenger

(Address) 140 W. Jewell, Kingman, KS 67068

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 95

Susan C. Rogers
Notary Public



Commission Expires: 9/19/98

RECEIVED
KANSAS CORPORATION COMMISSION
10-11-1995
OCT 11 1995