


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-077-30072-00⁰⁰ Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Harper County. Sec. 4 Twp. 33S Rge 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE. NE
Lease Owner Marion Corporation
Lease Name L. B. Parsons Well No. 1
Office Address Suite A Mid-Continent Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-23-65 19
Application for plugging filed 11-23-65 19
Application for plugging approved 11-23-65 19
Plugging commenced 11-23-65 19
Plugging completed 11-23-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4844 Feet
Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 211' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 200', set plug, cemented with 25 sacks cement
Filled hole with mud to 40', cemented with 10 sacks cement
put 2 sacks cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1965

CONSERVATION DIVISION
Wichita, Kansas

11-29-1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1965

My commission expires April 1, 1967

Ulanda Nichols
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Marion Corporation
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: L. B. PARSONS #1
 LOCATION: C SE NE Sec. 4-33S-6W
 HARPER COUNTY, KANSAS
 COMMENCED: 11-10-65
 COMPLETED: 11-23-65

| | | |
|------|-------------|--------------------------|
| 0 | 211 | Redbed |
| 211 | 250 | Shale |
| 250 | 470 | Redbed |
| 470 | 1090 | Shale, Shells |
| 1090 | 1105 | Anhydrite |
| 1105 | 1160 | Shale |
| 1160 | 1485 | Shale, Shells |
| 1485 | 1920 | Lime, Shale |
| 1920 | 3555 | Shale, Lime |
| 3555 | 3610 | Sand |
| 3610 | 3675 | Shale, Lime |
| 3675 | 3820 | Lime, Shale |
| 3820 | 3920 | Lime |
| 3920 | 3985 | Lime, Shale |
| 3985 | 4015 | Lime |
| 4015 | 4233 | Lime, Shale |
| 4233 | 4330 | Shale, Lime |
| 4330 | 4417 | Lime |
| 4417 | 4451 | Mississippi |
| 4451 | 4535 | Chert, Lime |
| 4535 | 4597 | Lime |
| 4597 | 4605 | Mississippi |
| 4605 | 4722 | Lime |
| 4722 | 4796 | Shale, Lime |
| 4796 | 4834 | Lime, Shale |
| 4834 | 4844 | Lime |
| | <u>4844</u> | <u>RTD - D. & A.</u> |

RECEIVED
 STATE CORPORATION COMMISSION

NOV 29 1965

CONSERVATION DIVISION
 Wichita, Kansas

11-29-1965

Set 8 5/8" used surface casing @ 211' with 200 sacks Posmix Sunset with 2% Gel

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the L. B. Parsons #1 well, located C SE NE of Section 4, Township 33 South, Range 6 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 26th day of November, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires: April 1, 1967