

15-077-20138-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 2 Twp. 33S Rge. (E) 6W(W)  
Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner PACIFIC OIL & GAS COMPANY  
Lease Name Downing Well No. 1-A  
Office Address Colcord Building, Oklahoma City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-19 1972  
Application for plugging filed 1-19 1972  
Application for plugging approved 1-19 1972  
Plugging commenced 1-19 1972  
Plugging completed 1-19 1972  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4790 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	257	8-5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Fluid to 240', 1/2 sx hulls, plug, 25 sx cement;  
Fluid to 40', 1/2 sx hulls, plug, 10 sx cement;  
Two sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 25 1972  
CONSERVATION DIVISION  
Wichita, Kansas

01-25-1972

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor D N B DRILLING, INC.  
Address 737 First National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF \_\_\_\_\_, ss.  
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James L. Donelson  
737 First Nat'l Bank Bldg., Wichita, Ks.  
(Address)

Subscribed and Sworn to before me this 24th day of January, 1972  
Ella Priess  
Notary Public

15-077-20138-00-00

DRILLERS' LOG

PACIFIC OIL & GAS COMPANY  
No. 1-A Downing  
C SW NE, Sec. 2-33S-6W  
Harper County, Kansas

Commenced: 1-10-72  
Completed: 1-19-72

Elev: 1322 K.B.

Surface Casing: 249' of  
8-5/8" cemented w/200 sx  
cement, 3% cc. 1-10-72

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	257
Shale	453
Shale & Salt	1010
Shale & Lime	1645
Lime & Shale	2304
Shale & Lime	2557
Lime & Shale	3226
Shale & Lime	3782
Lime	4052
Lime & Shale	4115
Lime	4169
Lime & Shale	4363
Lime	4668
Shale	4790 T.D.

RECEIVED  
STATE CONSERVATION COMMISSION  
JAN 25 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
01-25-1972

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 24th day of January, 1972.

My Commission Expires:  
August 25, 1972

*Ella Priess*  
Ella Priess, Notary Public

