

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-208,39-00-00

LEASE NAME Downing

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from N Section Line

660 Ft. from E Section Line
CN/2 NE NE

SEC. TWP. RGE. (E) or (W)

COUNTY Harper

Date Well Completed

Plugging Commenced 12-8-87

Plugging Completed 12-10-87

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center
Wichita, Kansas 67202

PHONE (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	323'	none
				5-1/2"	4741'	2754'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped bottom with 50 sacks cement and 1 sack hulls to 3780'. Shot pipe @2952', 2754', pulled a total of 65 joints of 5-1/2" casing. Plugged surface with 3 sacks hulls, 12 sacks gel and 120 sacks 60/40 pos, 2% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 66050 RECEIVED

Address P.O. Box 347 Chase, Kansas 67524 12-16-1987

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347
Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 14th day of December, 1987

Jane Hoover
Notary Public

My Commission Expires:




CONTRACTOR'S WELL LOG

OPERATOR: A. L. Abercrombie, Inc.
CONTRACTOR: Union Drilling Co., Inc.
LEASE NAME: Downing #1
LOCATION: 330' FNL & 660' FEL Sec. 2-33S-6W
Harper County, Kansas
COMMENCED: October 04, 1982
COMPLETED: October 15, 1982

0	320	Redbed	Set 8-5/8" @ 323' w/225 sacks
320	1165	Shale & Lime	common cement, 2% gel, 3% CC
1165	3154	Shale	
3154	3404	Shale & Lime	
3404	3837	Lime & Shale	
3837	4645	Lime	
4645	4733	Lime & Shale	
4733	4780	Lime	
4780		RTD	

We certify that the above foregoing is a true and correct copy of the log on the Downing #1, 330' FNL & 660' FEL Section 2-33S-6W, Harper County, Kansas.

Union Drilling Co., Inc.



R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 2nd day of November, 1982.

My appointment expires:

12-24-84


Shirley A. Gallegos
Notary Public



08-06-1987
AUG - 6 1987
CONSERVATION DIVISION
Wichita, Kansas