

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN E. BRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
BOYD C. LONDBERGH Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1963  
8-29-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. L. C. Drau of E. K. Edmiston has this date requested permission to plug the following described well:

Mr. Drau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 501 1st National Bank Bldg., Wichita, Kansas

Lease Name: Elsa "B" Well No. # 1

Location: 1/4 E/2 W/2 NW Sec. 35 Twp. 32 Rge. 14 (E)(W)W

County Barber Total Depth 4793 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Drau was instructed to plug the well as follows:

256' of 10 3/4" surface pipe, cemented with 250 sacks.

Fill hole with mud to 250', 1st cementing plug, 1 sack

hulls, cement with 25 sacks. Fill hole with mud to 40',

2nd cementing plug, 1 sack hulls, cement with 15 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent