

CPJ

State of Kansas



ROBERT S. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES C. GREENLEAF Commissioner
 DALE E. SAFFLE Commissioner
 RAYMOND E. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 1-29-70
 JAN 29 1970
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Brown of Gabbert-Jones Inc. has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drlg. Co.

Complete Address: 700 One Twenty Bldg. Wichita, Kans

Lease Name: Cline-Mills Well No. 2

Location: C/NW/NW Sec. 30 Twp. 32 Rge. 14 (E) (W) W

County: Barber Total Depth 4854 Oil Well

Gas Well Input Well SWD Well D & A ~~Est. No.~~ Wash Down 4534

Mr. Brown was instructed to plug the well as follows:

282 ft. of 8 5/8 surface pipe circulated with 225 sacks
cement. Did circulate. Fill hole to 260 ft. 1/2 sack hulls
plug, 25 sacks cement, fill hole to 40 ft. with mud, 1/2
sack hulls, plug, 10 sacks cement. 2 sacks cement in
rat hole

Very truly yours,

L. Russell Bihunter
 Conservation Division Agent