



CP2

15:135-70648-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1972
7-31-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Strata Drlg. has this
date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Four -Way Operating, Inc.

Complete Address: Box 698 Great Bend, Kansas

Lease Name: Elmore Well No. 3

Location: SE NE NE Sec. 12 Twp. 18 Rge. (E)(W) 21

County: Ness Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A XI Lost Hole

Mr. Steincamp was instructed to plug the well as follows:
Gas pits, circulate heavy mud, set cementing plug at 465' and displace
50 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Marney
Conservation Division Agent