

15-095 2000-00-000



State Corporation Commission  
CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WMA. H. AVON... Governor  
WILLIAM A. ... Chairman  
JAMES C. ... Commissioner  
HARRY G. ... Commissioner  
RAYMOND ... Secretary  
E. ... Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Mr. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 3, Kansas

Dear Sir:

Mr. Dike Hall of Sierra Petroleum Co. Inc. has this  
day requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company, Inc.

Complete Address: 211 N. Broadway, Wichita, Kansas

Land Name: Whitmer-Swingle Unit Well No. # 1

Location: C NW SW Sec. 2 Twp. 30 Rge. 9 (E)(W) W

County Kingman Total Depth 4260' Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

1 1/2" of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill  
hole with drilling mud to 225', 1st cementing plug, bridge with 1 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40'  
2nd cementing plug, bridge with 1 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent