



ROBERT B. HOCKING Governor
 DALE E. HARRIS Chairman
 JAMES V. SQUY Commissioner
 JAMES C. GERRARD Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 APR 22 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. F. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

April 18, 1968

Dear Sir:

Mr. Ace Hoberrecht of Ace Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Hoberrecht guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Co.

Complete Address: ¹⁴³⁴ 4154 Wichita Plaza Wichita, Kansas.

Lease Name: Lake B Well No. #1

Location: C-SW-NW Sec. 11 Twp. 32 Rge. 14W(E)(W)W

County: Barber Total Depth 4920' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberrecht was instructed to plug the well as follows:

900 ft of 8 5.8 " surface pipe circulated with 500 sacks cement. 4548 ft. of 4 1/2" long string. D. V. tool at 3415'

~~with 200 sacks cement. Bridge plug at 3100 ft. Top perforation~~

~~2848ft. Sand to 2830 ft. & 4 sacks cement. Mud to 850 ft. 10 ft.~~

~~rock bridge & 25 sacks cement. Mud to 40 ft. 10 ft. rock bridge & 10 sacks cement to surface.~~

Very truly yours,

Herbert J. Justice
 Conservation Division Agent