

CP2

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Musgrove of Bowers Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drlg. Co. Inc.

Complete Address: 1434 Wichita Plaza Bldg. Wichita, Ks

Lease Name: Lake D Well No. 1

Location: C SE/NE Sec. 11 Twp. 32s Rge. 14 (E)(W) W

County: Barber Total Depth 4068 Oil Well

Gas Well Input Well SWD Well D & A ~~Estimate~~

Mr. Musgrove was instructed to plug the well as follows:
Wash down Plug back 3620 ft.

1015 ft of 8 5/8 surface pipe cemented, circulated. Fill
hole to 300 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent