

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. EVID Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 MARY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

SEP 16 1963  
 9-16-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Inc has this

date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.Operator's full Name: Gear Production Co. Inc.Complete Address: 131 Laura, Wichita, KansasLease Name: Lake Well No. # 1Location: C SE NE Sec. 11 Twp. 32 Rge. 14 (E) (W) WCounty Barber Total Depth 4075 Oil Well XGas Well  Input Well  SWD Well  D & A  1st Hole Mr. Comstock was instructed to plug the well as follows:1015' of 8 5/8" surface pipe, cement circulated, 4068' of5 1/2" long string, cemented with 100 sacks. Plugged back to3920'. Top perforation 3891'. Sand to 3880', cement with5 sacks. Fill hole with mud to 300', 10' rock bridge.cement with 20 sacks. Fill hole with mud to 40', 10' rockbridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent