

1 040453

8-17 15-007-116665-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 3/14/53

S/2 NW SW, SEC. 7, T 32 S, R 14 W/E

1650 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Stumph-Smith Well # 3

Operator: National Cooperative Refinery Assoc.

County Barber 161.59

Name & Address 6000 W. 10th

Well Total Depth 4972 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 491

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 46357

Address 10th & Harrison, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 17 Month: 8 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4967' w/75 sx cement. Open hole at 4967-72'

1st plug sand 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 17 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4900' and dump 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

8 5/8" plated with 2" collar to pump through.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2231' of casing. (If additional description is necessary, use BACK of this form.)

INVOICED I will observe this plugging.

DATE: 8-29-90

NO. 29159

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1990
8-24-90
CONSERVATION DIVISION
WICHITA, KANSAS