

1 051043

4-23-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,787 - 0000

C W/2 SW, SEC. 2, T 23 S, R 31 W/E

1320 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883

Lease Name Nelson Well # 2-4

Operator: Sharon Resources, Inc.
Name &

County Finney 159.90

Address 7100 East Belleview Ave., Suite 201
Englewood, CO 80111

Well Total Depth 4920 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 479

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 23 Month: 4 Year: 19 88

Plugging proposal received from Rick Barringer

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2070-79'
1st plug at 2070' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
3rd plug at 500' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10 a.m. Day: 23 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement,

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 1200' with 80 sx cement,

3rd plug at 500' with 40 sx cement,

MAY 02 1988

4th plug at 40' with 10 sx cement,

5-2-88

5th plug to circulate rathole with 15 sx cement.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 5-6-88

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 20556

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. April 12, 1988 month day year

API Number 15-055-20,787 C-W/2-SW Sec. 2 Twp. 23 S. Rg. 31 East 1320 Ft. from South Line of Section 4620 Ft. from East Line of Section

OPERATOR: License # 9883 Sharon Resources, Inc. 7100 E. Belleview Ave #201 Englewood, CO 80111 Contact Person: Robert Elder Phone: (303) 694-4920

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 660 feet County: Finney Lease Name: Nelson Well #: 2-4 Ground surface elevation est. 2080 feet MSL. Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

CONTRACTOR: License # 5302 Red Tiger Drlg. Co. Wichita, KS 316-263-1201 Well Drilled For: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 180 Depth to bottom of usable water 1200 Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 450 Conductor pipe required Projected Total Depth 5000 feet Formation: Mississippi

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 3-16-88 Signature of Operator or Agent Title: Geologist

For KCC Use: Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. Y This Authorization Expires 9-18-88 Approved By 4-3-18-88

EFFECTIVE DATE: 3-23-88 Set 479 of 8 5/8 on 4-12-88

C-W/2-SW Sec. 2 Twp. 23 S. Rg. 31 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth, Formation, and SXS count. 1st plug @ 2070 ft deep, 50 SXS; 2nd plug @ 1200 ft deep, 80 SXS; 3rd plug @ 450 ft deep, 40 SXS; 4th plug @ 40 ft deep, 10 SXS; 5th plug @ rathole, 15 SXS.

Vertical log form with handwritten entries: PUSHER Rick Barage, TD 4920 FORMATION Miss, SURFACE PIPE 8 5/8 @ 479, ANHYDRITE 2070 ELEVATION, STARTING TIME & DATE 4-23-88 6:00 AM, COMPLETION TIME & DATE 4-23-88 10:00 AM, 1st PLUG @ 2070 FT. W/ 50 SX, 2nd PLUG @ 1200 FT. W/ 80 SX, 3rd PLUG @ 500 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Hall, TECHNICIAN RL

RECEIVED STATE CORPORATION COMMISSION MAY 02 1988 CONSERVATION DIVISION Wichita, Kansas