

1 031171

8-28 15-145-19008-000119

D-20,923

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE SW SE, SEC. 33, T 21 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

410 feet from S section line
1870 feet from E section line

Operator: Pratt Well Service, Inc.
Name & Address: P.O. Box 847
Pratt, KS 67124

Lease Name Peaker Well # 1 SWD
County Pawnee 136.40
Well Total Depth 4197 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 985

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2 p.m. Day: 28 Month: 8 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4189' w/100 sx cement, Open hole 4189-97'

1st plug set CIBP at 3800' and dump 2 sx cement on top of bridge plug,

2nd plug spot through 4 1/2" 50 sx cement at 950',

3rd plug at 450' with 25 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 6 p.m. Day: 28 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3800' and dumped 2 sx cement on top of bridge plug,

Spot through 4 1/2":

2nd plug at 950' with 50 sx cement,

3rd plug at 450' with 25 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 11 1991

CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1980' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED (copy to) observe this plugging.

DATE 9-18-91

Signed Steve Durrant (TECHNICIAN)

INV. NO. 33160