

1 050980

12-30-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20.963 0000
NE SW SE, SEC. 33, T 21 S, R 16 W XX'

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

990 feet from S section line

Operator: Berexco Inc.

1650 feet from E section line

Name:

Lease Name Osbourne Well # 1

Address 970 Fourth Financial Center

County Pawnee 124.90

Wichita, KS 67202

Well Total Depth 3843 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 982

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050.

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 30 Month: 12 Year: 19 87

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3839' Open hole 3839-3843'

1st plug sand back to 3750' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx cottonseed hulls, 10 sx gel and 125 sx Thrifty Mix cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 30 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3750' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 4 sx cottonseed hulls, 10 sx gel and 125 sx Thrifty Mix cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 300 psi. JAN 04 1988

Remarks: Used Thrifty Mix by B.J. Titan. Recovered 3000' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.) 01-09-88

INVOICED (do not XXXXX) describe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 1-11-88

INV. NO. 19474

12-30