

1060166 O

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,110 0000
N NE SW NE, SEC. 33, T 21 S, R 16 W/K

1110 feet from N/S ~~quarter~~
990 feet from W/E ~~quarter~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Arnold Well # 1

Operator: L.D. Drilling
Name & Address R. R. 1, Box 183B
Great Bend, KS 67530

County Pawnee
Well Total Depth 3920 127.40 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 986

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L. D. Drilling, Inc. License Number 6039

Address R. R. 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 18 Month: February Year: 19 84

Plugging proposal received from Don Poppe

(company name) L.D. Drilling (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1030' with 50 sx cement

2nd plug at 520' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 pm Day: 18 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1030' with 50 sx cement, 2nd plug at 520' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rathole with 15 sx cement. Plug water well
with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1984

Remarks: Use 60/40 Pozmix 2% gel 3% cc. by Halliburton CONSERVATION DIVISION
(if additional description is necessary, use BACK of this form)

INVOICED
did not observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 2-23-84

INV. NO. 0343