

1080568

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,037 0000
W/2 E/2 SE, SEC. 33, T 21 S, R 16 (W/R)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: Berexco Inc.
Name & Address 970 Fourth Financial Center
Wichita, KS 67202

1320 feet from S section line

1650 feet from E section line

Lease Name Marie Well # 1

County Pawnee 125.06

Well Total Depth 3848 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1002

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 20 Month: 11 Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3845' Open hole at 3845-52' Elevation 2804' KB

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 1/2 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Bud Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:05 p.m. Day: 20 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx light cement.

Maximum pressure 1000 psi and shut in 850 psi.

NOV 20 1986
11-26-86

Remarks: Used Thrifty Light cement by B.J. Titan. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed J. A. Metz
(TECHNICIAN)

DATE 12-3-86

QTY. NO. 15446