

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21185-00-00  
Spot: SENESENW Sec/Twnshp/Rge: 33-21S-16W  
1890 feet from N Section Line, 2410 feet from W Section Line  
Lease/Unit Name: WESTHOFF Well Number: 2  
County: PAWNEE Total Vertical Depth: 3900 feet

Operator License No.: 100  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 980  
Production: Size 5.5 feet: 3895 WITH 250 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/09/2001 1:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BOTTOM TO 3840' AND DUMP 5 SX CMT ON TOP OF SAND. FREEPOINT PIPE. PULL PIPE TO 1000'. SPOT 10 SX GEL - 50 SX CMT. PULL PIPE TO 400'. SPOT 50 SX CMT. PULL PIPE TO 40'. SPOT 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/09/2001 2:45 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3895-3900'. SANDED TO 3820' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1000' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2426' OF 5 1/2" CASING.

Plugged through: CSG

District: 01 KANSAS CORPORATION COMMISSION

Signed

*Richard W. Lacey*

(TECHNICIAN)

JUL 16 2001

JUL 12 2001

CONSERVATION DIVISION

Form CP-2/3

*MD*