

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21175-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 33-21S-16W
1790 feet from N Section Line, 2265 feet from W Section Line
Lease/Unit Name: WESTOFF - RG Well Number: 1
County: PAWNEE Total Vertical Depth: 3895 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 966
Production: Size 5.5 feet: 3895 WITH 250 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/06/2001 10:50 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed
Plugging
Method:

SAND BOTTOM TO 3840' AND DUMP 5 SX CMT ON TOP OF SAND. FREEPOINT PIPE. PULL PIPE TO 1000'.
SPOT 10 SX GEL - 50 SX CMT. PULL PIPE TO 400'. SPOT 50 SX CMT. PULL PIPE TO 40'. SPOT 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/06/2001 12:10 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3895-3900'. SANDED TO 3820' & DUMP 5 SX CMT WITH A DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1000' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2006' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Richard W. Lacey

(TECHNICIAN)

JUL 16 2001

JUL 12 2001

CONSERVATION DIVISION

Form D-273