

1 060747

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,648/0001

SE NE NE , SEC. 12 , T 18 S, R 21 (W/X)

4290 feet from (S) section line

330 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # ~~9360~~ 9810

Lease Name Elmore Ryan Well # 1

Operator: Castle Resources

County Ness

Name & Address

Well Total Depth 4200 136.50 feet

P. O. Box 90

Conductor Pipe: Size _____ feet

Hays, KS 67601

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A OWWO

Other well as hereinafter indicated _____

Plugging Contractor Bill's Well Service License Number 6997

Address P. O. Box 37, Cordell, KS 67630

Company to plug at: Hour: 4:30 pm Day: 18 Month: December Year: 19 85

Plugging proposal received from Jerry Green

(company name) Castle Resources (phone) 913-625-5155

were: 4 1/2" at 4197' (cement circulated) Perfs at 4114-20'

Squeeze well with 1 sack hulls, 50 sx cement, 7 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:15 pm Day: 18 Month: December Year: 19 85

ACTUAL PLUGGING REPORT Squeezed well with 1 sack hulls, 50 sx cement, 7 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 1000 psi and shut in 1000 psi

Remarks: No Recovery. Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

Signed Paul A. Luthi (TECHNICIAN)

DATE DEC 27 1985

INV. NO. 11733

12-18 FEB 5 1986

DEC 27 1985 MAR 27 1986